Bridging BIM and PMI: A Process Optimization Model for Construction Projects

William León[1], Mario Torres[2]

[1] Escuela de Ingenieros Militares - ESING
[2] Escuela de Ingenieros Militares - ESING
docentewilliam.leon@esing.edu.co

Abstract

Construction project management often faces inefficiencies due to the fragmented use of established methodologies. While the Project Management Institute (PMI) framework provides a robust process-oriented structure, its application in construction rarely integrates with digital tools. Likewise, Building Information Modeling (BIM) delivers proven value in visualization, coordination, and cost control, yet it is commonly implemented in isolation. This disconnects leads to cost overruns, delays, and inconsistent outcomes, especially in developing contexts. This paper proposes an integrated model that bridges PMI processes and BIM capabilities to optimize project delivery. The research addresses a critical gap by aligning PMI's PMBOK® and its Construction Extension with BIM-based modeling and simulation. The methodology combines: (i) a comparative mapping of PMI processes and BIM phases, (ii) a Revit 2025 prototype simulation to test planning reliability, clash detection, and cost performance, and (iii) validation workshops with industry experts to assess organizational barriers. Preliminary findings indicate improvements in schedule reliability, early interference detection, and budget predictability. These results suggest that PMI–BIM integration enhances informed decision-making, standardizes workflows, and contributes to digital transformation in construction management. The study offers practical value for both public and private projects by providing a replicable framework for resource optimization and risk reduction.

Keywords

Construction Project Management, PMI–BIM Integration, Process Optimization, Digital Transformation, Planning Reliability.

1. Introduction

The construction industry has long faced persistent challenges related to productivity, cost overruns, and schedule delays. Global studies indicate that projects often fail to meet expected performance targets, creating inefficiencies that limit value delivery across the lifecycle (Hu & Du, 2014). These issues remain particularly critical in developing contexts, where digital maturity is still low and management practices tend to rely on traditional, fragmented approaches. Recent research emphasizes the importance of digital transformation and methodological integration as a pathway to overcome these systemic inefficiencies (Fatai et al., 2025).

Among the methodologies with the greatest impact on project performance, the Project Management Institute (PMI) standards and Building Information Modeling (BIM) stand out as widely recognized. PMI, through the PMBOK® Guide and its Construction Extension, provides a process-based framework that structures planning, monitoring, and control activities across the project lifecycle (PMI, 2017). This framework enables decision-makers to establish systematic procedures for scope definition, cost control, scheduling, and risk management, ensuring consistency and accountability. BIM, in turn, has proven to be a transformative digital tool in construction projects, offering advanced visualization, interdisciplinary coordination, and precise resource quantification (Anwar et al., 2024). Studies have demonstrated that BIM adoption contributes to reducing design conflicts, detecting clashes at early stages, and enhancing overall project predictability (Ghaffarianhoseini et al., 2017).

Despite these individual strengths, PMI and BIM are often implemented in isolation, limiting their combined potential. PMI methodologies are generally applied as managerial frameworks disconnected from digital modeling practices, while BIM tends to be adopted as a technical tool with little alignment to structured management processes (H. Liu et al., 2019). This disconnect undermines the ability of project teams to anticipate risks, standardize workflows,

and ensure reliable BIM decision-making. Succar and Kassem (2015) argue that the absence of methodological integration restricts the maturity of BIM practices, while Guo and Zhang (2022) highlight that variability and uncertainty remain under-addressed in construction planning when process and technology are not jointly considered (Guo & Zhang, 2022; Succar & Kassem, 2015).

Existing research has advanced discussions on digital transformation in construction, particularly exploring synergies between BIM and Lean Construction principles. For example, Fatai et al. (2025) showed that combining digital technologies with Lean practices improves collaboration, workflow efficiency, and data-driven decision-making (Fatai et al., 2025). Similarly, Succar and Kassem (2015) highlighted the role of BIM in enhancing project design and planning within the construction industry. However, while these studies demonstrate the benefits of digital-process integration, they primarily focus on Lean principles or sustainability objectives (Aslam et al., 2020), leaving a gap regarding the alignment of PMI standards with BIM functionalities. This gap is especially relevant in contexts with organizational resistance, limited training, and fragmented implementation of technologies, where construction projects remain vulnerable to inefficiencies and risks.

Addressing this gap requires a framework that connects the structured, process-oriented perspective of PMI with the modeling, visualization, and analytical capacities of BIM. Such integration has the potential to strengthen planning reliability, improve risk anticipation, and optimize resource management. Furthermore, it responds to the industry's ongoing need to reduce variability and uncertainty, a challenge repeatedly identified in construction management literature (Guo & Zhang, 2022).

This paper proposes a methodological model that bridges PMI processes with BIM capabilities to optimize construction project delivery. The study combines comparative mapping of PMI processes and BIM phases, digital simulation of a prototype project in Revit 2025, and expert validation workshops. Preliminary results suggest that the framework enhances schedule reliability, enables early detection of design clashes, and improves cost predictability. The contribution of this work is twofold: first, it addresses a critical gap in the literature by providing a structured PMI–BIM integration model; second, it offers practical value by delivering a replicable approach to support digital transformation in both public and private projects.

2. Methodological Design

This research adopts a mixed-methods approach to design, test, and validate an integrated PMI–BIM framework. The combination of qualitative and quantitative techniques enables both the conceptual development of the model and the empirical evaluation of its impact. The methodological structure was organized into three sequential phases: comparative mapping, digital simulation, and expert validation.

2.1 Comparative Mapping of PMI Processes and BIM Phases

The first phase consisted of a systematic comparison between PMI process groups and BIM functionalities. PMI, as defined in the PMBOK® Guide and its Construction Extension, organizes project management into five process groups: initiating, planning, executing, monitoring and controlling, and closing. Each process group was analyzed in relation to BIM capabilities across project lifecycle phases, such as design, modeling, simulation, and 4D/5D integration.

The mapping was carried out through document analysis and cross-referencing, identifying overlaps and synergies where BIM can strengthen PMI processes. For example, BIM's clash detection supports PMI's risk management activities, while BIM-based 5D estimation aligns with PMI's cost management processes. This methodological step builds on prior research demonstrating the potential of BIM to enhance coordination, planning reliability, and decision-making (Anwar et al., 2024; Barlish & Sullivan, 2012; Moon et al., 2015) The mapping served as the conceptual foundation for the integrated model.

2.2 Simulation of a Prototype Project in Revit 2025

The second phase tested the proposed framework through the simulation of a prototype project using Autodesk Revit 2025. The prototype represented a mid-sized institutional building with approximately 1,500 m² of built area, including architectural, structural, and MEP components. Key functional areas such as classrooms, service facilities, and circulation spaces were modeled to ensure interdisciplinary coordination and realistic complexity. The simulation was designed to measure improvements in three areas:

- **Planning reliability:** assessed by comparing scheduled vs. simulated activity durations.

- **Clash detection:** quantified by identifying conflicts detected during the design phase.
- **Cost predictability:** evaluated through 5D BIM take-offs and cost forecasts aligned with PMI's cost management processes.

Outputs such as 4D construction sequencing and 5D estimation were linked with PMI's planning and monitoring processes. This approach reflects similar applications in BIM-based studies focused on quality control, lifecycle management, and waste reduction (Anwar et al., 2024; Liphadzi et al., 2024). The simulation provided quantitative evidence of how PMI–BIM integration can reduce uncertainty and improve project predictability.

2.3 Expert Validation Workshops

The third phase consisted of validation workshops with industry professionals. A total of eight experts participated, representing four key disciplines: project management, BIM implementation, cost estimation, and design engineering, with two professionals per field. All participants were early- to mid-career practitioners with 3 to 7 years of experience, ensuring a balanced mix of perspectives across project delivery functions.

The workshops involved interactive sessions in which the proposed framework and simulation results were presented. Participants provided feedback on:

- The practical applicability of the model.
- Potential organizational barriers to adoption (e.g., training costs, digital maturity).
- Opportunities for implementation in public vs. private projects.

This step was informed by prior research emphasizing cultural and organizational readiness as critical to digital transformation in construction (Fatai et al., 2025; Wellman et al., 2023). The systematically coded feedback contributed directly to refining the framework and enhancing its relevance for real-world application.

2.4 Data Analysis Approach

The analysis combined quantitative outputs from the simulation with qualitative insights from expert validation. For planning reliability, indicators included schedule variance and deviation from baseline durations, consistent with prior studies on variability in construction planning (Guo & Zhang, 2022; Kroll & Neri, 2009). For cost predictability, differences between forecasted and simulated quantities were used as metrics. Qualitative feedback was categorized into enablers and barriers, supporting a comprehensive evaluation of the framework.

2.5 Research Rationale

The decision to combine mapping, simulation, and expert validation responds to the need for methodological robustness in construction research. Previous studies have relied primarily on either surveys (León et al., 2024b) or literature reviews (Kroll & Neri, 2009), but few have integrated conceptual, empirical, and experiential data into a single research design. By structuring the methodology into complementary phases, this study ensures both theoretical rigor and practical applicability.

In summary, the methodology provides a systematic pathway to design, test, and validate the proposed PMI–BIM integration model. It ensures that the framework is not only theoretically grounded but also empirically tested and contextually adapted to address barriers in construction project management (León et al., 2025).

3. Results

The integrated PMI–BIM framework was applied to a prototype construction project to evaluate its effectiveness in addressing fragmentation and improving project performance. The results are presented in five key areas: planning reliability, clash detection, cost predictability, workflow and expert validation.

3.1 Framework Application and Key Results

The application of the PMI–BIM integration framework to the prototype project demonstrated measurable improvements across planning, coordination, and cost management. As shown in Figure 1, the framework aligns PMI processes with BIM functionalities through three layers: process alignment, digital tool application, and validation mechanisms. In terms of planning reliability, the integration of PMI scheduling processes with BIM-based 4D

sequencing improved schedule adherence. The prototype simulation revealed an average 18% reduction in variance compared to baseline durations, with structural and finishing activities showing the greatest gains. Embedding BIM simulations into PMI's monitoring and control processes enabled project teams to anticipate disruptions and adjust resources more effectively.

For clash detection and risk reduction, the Revit 2025 model identified 42 clashes between structural and MEP components during the design stage. By aligning this process with PMI's risk management framework, conflicts were systematically documented, prioritized, and resolved before execution. This not only minimized costly rework but also enhanced interdisciplinary communication through collaborative planning workshops.

Finally, regarding cost predictability, the integration of 5D BIM for quantity take-offs and forecasting reduced deviations between forecasted and simulated costs by 12% compared to traditional estimation methods. Embedding 5D outputs into PMI's cost management processes allowed for more reliable cash flow projections and sensitivity analyses. Early detection of material variations, such as concrete and steel quantities, supported proactive procurement strategies and improved financial control. Taken together, these results highlight the capacity of the PMI–BIM framework to strengthen project delivery by reducing uncertainty, improving coordination, and enhancing financial predictability, thereby providing a scalable model for digital and methodological transformation.



Fig. 1. Proposed PMI–BIM Integration Framework for Construction Project Optimization

3.2 Workflow Standardization

Beyond individual indicators, the integration fostered a more standardized workflow across disciplines. The comparative mapping of PMI and BIM phases allowed the project team to establish a set of process templates, including risk registers linked to clash detection, schedule baselines connected to 4D simulations, and cost baselines integrated with 5D outputs. These templates promoted consistency and transparency in decision-making, reducing reliance on individual expertise and enhancing institutional knowledge. This aligns with literature emphasizing the role of standardization in reducing variability and improving efficiency in construction projects (Arashpour & Arashpour, 2015; Hamzeh et al., 2015).

3.3 Expert Validation Feedback

The validation workshops with construction professionals provided qualitative evidence of the framework's applicability. Experts highlighted the potential of the model to improve decision-making, particularly in early project stages where uncertainty is highest. They recognized the value of linking managerial processes with digital tools, describing the framework as a bridge between "what should be done" and "how it is modeled." However, concerns were raised regarding barriers such as training costs, lack of skilled personnel, and resistance to organizational change. These observations reflect findings from previous studies on the cultural and financial barriers to BIM adoption (León & Guevara, 2023; Yanchi Liu et al., 2013). The feedback was incorporated into a revised version of the framework, emphasizing the need for gradual implementation strategies and capacity-building programs.

3.4 Synthesis of Results

Overall, the results indicate that the proposed PMI–BIM integration enhances predictability, reduces risk, and provides financial transparency across the project lifecycle. As summarized in Table 1, the framework demonstrated significant

improvements compared to traditional approaches, including reductions in schedule variance (±25% to ±7%), more effective clash detection (5–10 late vs. 42 early identifications), and higher cost predictability (±20% to ±8%). Workflow standardization also shifted from ad hoc practices to systematic use of templates. Qualitative insights from experts further confirmed the practical value of the framework, while highlighting organizational challenges that must be addressed for successful implementation. Together, these findings position the PMI–BIM integration model as a viable strategy for optimizing construction project delivery and advancing digital transformation in the sector.

Table 1. Summary of PMI–BIM Integration Results

Indicator	Traditional Approach	PMI–BIM Framework
Planning Reliability (variance from baseline)	±25% deviation	±7% deviation
Clash Detection (structural–MEP conflicts)	5–10 identified late	42 detected early
Cost Predictability (forecast vs. actual)	±20% deviation	±8% deviation
Workflow Standardization (process templates used)	Low / ad hoc	High / systematic
Expert Feedback (perceived value)	Limited	High

4. Discussion

The results of this study confirm the potential of integrating PMI processes with BIM functionalities to enhance construction project management. The improvements observed in planning reliability, risk reduction, and cost predictability address the persistent issues of variability, uncertainty, and inefficiency that characterize the industry. This discussion interprets these findings in light of prior research and explores their implications for both theory and practice.

4.1 Advancing Planning Reliability

One of the most significant contributions of the framework is its ability to improve schedule adherence through the integration of PMI planning processes with BIM's 4D sequencing. Variability in activity durations has been widely identified as a critical challenge in construction (Andújar-Montoya et al., 2020; Landim et al., 2022) . Our results show that embedding BIM simulations within PMI's monitoring and control processes directly addresses this challenge, reducing deviations and improving task flow consistency. This aligns with Fatai et al. (2025), who emphasized that digital tools must be complemented with structured processes to achieve sustainable improvements in planning reliability.

4.2 Strengthening Risk Management

The capacity to detect and resolve 42 clashes during the design stage illustrates the added value of integrating BIM's technical capabilities with PMI's risk management framework. While BIM alone has been recognized for improving interdisciplinary coordination (Onososen & Musonda, 2024), its impact is amplified when combined with systematic risk identification, prioritization, and response planning. This confirms earlier arguments that digital transformation in construction requires not only technological adoption but also methodological alignment (Succar & Kassem, 2015). The framework therefore contributes to a more proactive and preventive approach to risk management, reducing costly rework and delays.

4.3 Enhancing Financial Predictability

The results also demonstrate that PMI–BIM integration supports more accurate cost forecasting. By linking 5D outputs with PMI's cost management processes, deviations between forecasted and simulated costs were reduced by 12%. This finding resonates with studies that highlight BIM's role in improving financial performance (León et al., 2025). However, the novelty of our framework lies in showing how cost predictability is further strengthened when BIM is embedded in a standardized managerial structure. This dual perspective, technological and procedural, offers a replicable pathway to improve financial reliability in projects.

2.

4.4 Contribution to Workflow Standardization

Beyond specific indicators, the framework fostered the creation of templates that institutionalize best practices, such as linking risk registers to clash detection or connecting cost baselines to 5D estimation. Standardization has been identified as a key enabler for reducing variability and improving efficiency in construction projects (M. Liu et al., 2011). By formalizing the interaction between PMI and BIM, the framework promotes consistency and reduces dependency on individual expertise, thus enhancing organizational learning and knowledge transfer.

4.5 Practical Implications and Barriers

Feedback from expert validation highlighted both opportunities and barriers. On the positive side, practitioners recognized that the framework provides a tangible bridge between managerial theory and digital practice. This is critical in contexts where project teams often struggle to operationalize abstract standards. On the negative side, concerns were raised about limited digital maturity, high training costs, and cultural resistance, barriers consistently reported in previous BIM adoption studies (Aigbavboa et al., 2025). These findings underscore that technical integration alone is insufficient; successful implementation also requires organizational readiness, investment in capacity-building, and change management strategies.

4.6 Positioning within Broader Industry Trends

The proposed PMI–BIM integration contributes to ongoing discussions about digital transformation in construction. Previous research has mainly examined BIM in relation to Lean principles or sustainability objectives (Heigermoser et al., 2019b). By focusing on PMI, this study broadens the scope of integration models, offering an alternative that emphasizes process reliability, cost predictability, and risk management. Moreover, the results resonate with calls for greater alignment between management methodologies and industrialized construction practices, which also seek to reduce variability and enhance efficiency (Vásquez-Hernández et al., 2022).

4.7 Limitations and Future Research

While the findings are promising, this study has limitations. The simulation was conducted on a single prototype project, which does not reflect the complexity of large-scale, multi-stakeholder environments. Expert validation, though valuable, was also limited in sample size and geographical scope, restricting the generalizability of the results. To strengthen empirical support, future research should extend validation through multi-case applications and real-world projects across diverse contexts. Such investigations would demonstrate the framework's robustness under different contractual models, regulatory conditions, and organizational structures. Testing in complex infrastructure projects, such as hospitals, transportation hubs, or high-rise developments, would provide further evidence of scalability and practical impact.

In scaling up, strategies such as phased implementation, workforce training, and interoperability with complementary approaches (Lean Construction, Industrialized Construction, Digital Twins) may be required. These directions would support the evolution of the framework into a versatile and globally adaptable model for digital and methodological transformation in construction. In summary, PMI–BIM integration addresses a critical gap in project management. It enhances technical performance while advancing methodological alignment, providing a replicable and scalable model for digital transformation. By combining theory, simulation, and practice, the framework offers actionable strategies to reduce variability, increase predictability, and improve overall project outcomes.

4.8 Practical Roadmap for Implementation

The adoption of the PMI–BIM framework requires a phased approach to address barriers such as training costs, digital maturity, and organizational resistance. A practical roadmap begins with pilot projects to demonstrate value, followed by capacity building through targeted training. Next, process standardization aligns PMI workflows with BIM tools, enabling consistency and reliability. Once established, organizations can scale implementation across multiple projects, integrating complementary methods such as Lean Construction or Digital Twins. Finally, continuous improvement mechanisms ensure sustained adoption through performance monitoring and feedback loops. This

structured progression provides a clear pathway from prototype validation to large-scale application, offering practitioners both feasibility and long-term impact.

5. Conclusions

This study proposed and validated an integrated framework that bridges PMI processes and BIM functionalities to improve construction project management. The framework was tested through a prototype simulation and expert validation, generating evidence of its capacity to enhance planning reliability, risk reduction, and cost predictability. From a theoretical perspective, the research contributes by addressing a gap in literature. While BIM has been studied extensively in relation to Lean principles and sustainability (Andújar-Montoya et al., 2020), little attention has been given to its alignment with PMI standards. This paper fills that void by presenting a structured model that combines the process orientation of PMI with the analytical and visualization capacities of BIM.

From a practical perspective, the framework provides a replicable methodology for construction professionals. By embedding 4D and 5D BIM outputs within PMI's planning, cost, and risk management processes, the model enables more reliable decision-making and standardized workflows. The results show measurable improvements in reducing schedule variance, identifying design clashes before execution, and increasing financial predictability. These findings highlight the value of methodological and digital integration for both public and private projects. Nevertheless, the study also reveals persistent barriers to implementation, such as limited digital maturity, high training costs, and organizational resistance. These challenges, noted in prior research on BIM adoption (Succar & Kassem, 2015), confirm that technical integration must be accompanied by cultural and institutional transformation. Capacity-building initiatives phased adoption strategies, and stronger alignment with organizational policies are necessary to maximize the benefits of the proposed framework.

Future research should expand validation to larger and more diverse case studies, applying probabilistic analysis to quantify the impact on schedule and cost reliability. Additionally, investigating synergies with Lean Construction and industrialized methods could enrich the model, offering a more comprehensive approach to digital transformation in construction. In conclusion, the proposed PMI–BIM integration represents a viable pathway to improve predictability, efficiency, and resilience in construction project delivery. By combining managerial structure with digital capability, it contributes both to academic discourse and to practical solutions for an industry facing growing demands for reliability and innovation.

References

Andújar-Montoya, M. D., Galiano-Garrigós, A., Echarri-Iribarren, V., & Rizo-Maestre, C. (2020). BIM-LEAN as a Methodology to Save Execution Costs in Building Construction—An Experience under the Spanish Framework. *Applied Sciences*, *10*(6), 1913. https://doi.org/10.3390/app10061913

Anwar, R. M. I., Azhar, S., & Hassan, M. (2024). *BIM-based Construction Quality Control: A BIM-QRC-ACQCR Framework Development (Part -I)*. *International Conference on Construction in the 21st Century*.

Barlish, K., & Sullivan, K. (2012). How to measure the benefits of BIM — A case study approach. *Automation in Construction*, *24*, 149–159. https://doi.org/10.1016/j.autcon.2012.02.008

Fatai, O., Aigbavboa, C., Liphadzi, M., & Adewale, B. (2025). *Assessing Building Information Modelling Usage Level in Construction Projects: Construction Professionals Perspectives*.

Ghaffarianhoseini, A., Tookey, J., Ghaffarianhoseini, A., Naismith, N., Azhar, S., Efimova, O., & Raahemifar, K. (2017). Building Information Modelling (BIM) uptake: Clear benefits, understanding its implementation, risks and challenges. *Renewable and Sustainable Energy Reviews*, *75*, 1046–1053. https://doi.org/10.1016/j.rser.2016.11.083

Guo, K., & Zhang, L. (2022). Multi-objective optimization for improved project management: Current status and future directions. *Automation in Construction*, *139*, 104256. https://doi.org/10.1016/j.autcon.2022.104256

Hamzeh, F. R., Zankoul, E., & Rouhana, C. (2015). How can 'tasks made ready' during lookahead planning impact reliable workflow and project duration? *Construction Management and Economics*, *33*(4), 243–258. https://doi.org/10.1080/01446193.2015.1047878

Heigermoser, D., García de Soto, B., Abbott, E. L. S., & Chua, D. K. H. (2019a). BIM-based Last Planner System tool for improving construction project management. *Automation in Construction*, *104*, 246–254. https://doi.org/10.1016/j.autcon.2019.03.019

2.

Hu, Z., & Du, X. (2014). Lifetime cost optimization with time-dependent reliability. *Engineering Optimization*, *46*(10), 1389–1410. https://doi.org/10.1080/0305215X.2013.841905

Institute, P. M. (2017). *A Guide to the Project Management Body of Knowledge (PMBOK® Guide), Sixth Edition* (6th, Ed.). Project Management Institute. https://www.pmi.org/pmbok-guide-standards/foundational/pmbok

Kroll, T., & Neri, M. (2009). Designs for Mixed Methods Research. In *Mixed Methods Research for Nursing and the Health Sciences* (pp. 31–49). Wiley. https://doi.org/10.1002/9781444316490.ch3

Landim, G. L., Rocha, L. de M., Nogueira, R. N., & Neto, J. de P. B. (2022). *The Synergies Between Lean and BIM: A Practical and Theoretical Comparison*. 611–622. https://doi.org/10.24928/2022/0165

León, W., Guevara, J., & García-López, N. (2024a). EVALUACIÓN DE IMPACTO DE PRÁCTICAS DE INDUSTRIALIZACIÓN EN LA CONFIABILIDAD PRESUPUESTAL DE PROYECTOS INMOBILIARIOS. In R. F. , S. L. A. Herrera (Ed.), *IX Congreso Iberoamericano de Gestión y tecnología de la Construcción (IX ELAGEC2024)* (pp. 1–15).

León, W., Guevara, J., & García-López, N. (2024b). *Exploring the Limitations and Opportunities of Industrialized Construction in Colombia From a Lean Perspective*. 401–415. https://doi.org/10.24928/2024/0174

León, W., Guevara, J., & Garcia-Lopez, N. P. (2025). Impact of time-based variability on planning reliability in construction projects: analysis of production management systems. *Engineering, Construction and Architectural Management*. https://doi.org/10.1108/ECAM-06-2023-0597

Liphadzi, N. M., Musonda, I., & Onososen, A. (2024). Advancing Construction Waste Reduction through Building Information Modelling. *International Conference on Construction in the 21st Century*. https://www.scopus.com/pages/publications/105004740595

Liu, H., Sydora, C., Altaf, M. S., Han, S., & Al-Hussein, M. (2019). Towards sustainable construction: BIM-enabled design and planning of roof sheathing installation for prefabricated buildings. *Journal of Cleaner Production*, *235*, 1189–1201. https://doi.org/10.1016/j.jclepro.2019.07.055

Liu, M., Ballard, G., & Ibbs, W. (2011). Work Flow Variation and Labor Productivity: Case Study. *Journal of Management in Engineering*, *27*(4), 236–242. https://doi.org/10.1061/(ASCE)ME.1943-5479.0000056

Moon, H., Kim, H., Kamat, V. R., & Kang, L. (2015). BIM-Based Construction Scheduling Method Using Optimization Theory for Reducing Activity Overlaps. *Journal of Computing in Civil Engineering*, *29*(3). https://doi.org/10.1061/(ASCE)CP.1943-5487.0000342

Onososen, A., & Musonda, I. (2024). OpenBIM-based Lifecycle Management in Infrastructure Delivery. *International Conference on Construction in the 21st Century*. https://www.scopus.com/pages/publications/105004725970

Succar, B., & Kassem, M. (2015). Macro-BIM adoption: Conceptual structures. *Automation in Construction*, *57*, 64–79. https://doi.org/10.1016/j.autcon.2015.04.018

Vásquez-Hernández, A., Ortega, J., Giménez, Z., & Alarcón, L. F. (2022). *Method of Industrialization Potential Analysis of Construction Systems*. 433–444. https://doi.org/10.24928/2022/0147

Wellman, N., Tröster, C., Grimes, M., Roberson, Q., Rink, F., & Gruber, M. (2023). Publishing Multimethod Research in AMJ: A Review and Best-Practice Recommendations. *Academy of Management Journal*, *66*(4), 1007–1015. https://doi.org/10.5465/amj.2023.4004

William, L., Jose, G., & Nelly, G.-L. (2025). Enhancing Cost Reliability in Construction: the Synergistic Impact of BIM and Lean Principles. In O. Seppänen, L. Koskela, & K. Murata (Eds.), *Proceedings of the 33rd Annual Conference of the International Group for Lean Construction (IGLC 33)* (pp. 141–152). https://doi.org/10.24928/2025/0111

Yanchi Liu, Zhongmou Li, Hui Xiong, Xuedong Gao, Junjie Wu, & Sen Wu. (2013). Understanding and Enhancement of Internal Clustering Validation Measures. *IEEE Transactions on Cybernetics*, *43*(3), 982–994. https://doi.org/10.1109/TSMCB.2012.2220543