

1 **Best Management Practices in Design, Construction, and**
2 **Maintenance of Mechanical Systems in Data Centers**

3 Prabha Sharma¹, Scott Kramer¹, Junshan Liu¹

4 ¹ Auburn University, Auburn, AL 36849, USA
5 kramesw@auburn.edu

6 **Abstract.** This purpose of this research study is to evaluate the challenges faced
7 during the project definition, design, construction, and maintenance phase of
8 mechanical systems projects for new Data Centers or existing Data Centers.
9 Construction industry professionals, design professionals, data center
10 management and engineering personnel were surveyed. The survey questionnaire
11 comprised of 27 questions and focused on the following themes: General
12 information and respondent's area of knowledge and experience, Overall
13 Management Challenges in Data Centers, Challenges specific to data center
14 mechanical systems, standard management practices and processes employed in
15 data center mechanical projects and recommendation and suggestions to arrive at
16 best management practices in mechanical systems projects for data centers. The
17 results of the survey were evaluated to arrive at best management practices to
18 better assist in building reliable data centers.

19 **Keywords:** Data centers, mechanical systems, best management practices

20 **1 Introduction**

21 Data centers are mission critical facilities that typically contain thousands of data
22 processing equipment, such as servers, switches, and routers. In recent years, there has
23 been a boom in data center usage, leading their energy consumption to grow by about
24 10% a year continuously. The heat generated in these data centers must be removed to
25 prevent high temperatures from degrading their reliability, which would cost additional
26 energy [1]. Data center owners and operators face high stakes challenges, as poor
27 decisions can lead to difficulties that must be dealt with for decades [2].

28 Failure of any mission critical system due to the disability in equipment, software,
29 process, results in the failure of business operations. It is not rare for a data center power
30 outage to happen. According to a survey that is conducted by the Emerson Network
31 Power and Ponemon Institute in 2010 95% of the data centers has unplanned outages.
32 The outage can cost a business an average of \$300,000 in just 1 hour (\$5,600 per
33 minute). Respondents averaged 2.48 complete data center shutdowns over a two-year
34 period, with an average duration of 107 mins. The root cause analysis shows that among
35 the top seven causes of unplanned outage are insufficient cooling, load capacity issues,
36 and heat-related/computer room air conditioner (CRAC) failure.

37 **2 Research Objective and Data Centers**

38 The objective of this study is to identify factors and challenges associated with
39 mechanical systems projects in data centers and to establish best management practices
40 that would focus on a dynamic and collaborative approach involving all stakeholders
41 in delivering a data center that would meet the desired needs, thus eliminating the need
42 for redesign or upgrade in a couple of years. Whether one is planning to build a new
43 data center, leasing capacity in a collocated data center, or retrofitting an existing data
44 center to expand its capacity, careful planning, coordination, and collaboration needs
45 to happen amongst all stakeholders to understand the requirements. This is the
46 backbone to laying the foundation of success for mechanical system in data centers.

47 **3 Data Center Design Requirements**

48 **3.1 Tier Classifications**

49 There are four levels of a data center, based on the infrastructure requirements. The
50 simplest is a Level 1 data center, which is basically a server room. The most stringent
51 level is a Level 4 data center, which is designed to host the most mission critical
52 computer systems, with the ability to continuously operate for an indefinite period
53 during power outages [3].

54 Tier 1: Basic – Per TIA-942-A (2014 edition), the HVAC system of a Basic facility
55 includes single or multiple air conditioning units with the combined cooling capacity
56 to maintain critical space temperature with no redundant units. If a generator is
57 provided, all air-conditioning equipment should be powered by the standby generator
58 system. Associated with less than 28.8 hours of downtime/year.

59 Tier 2: Redundant Components – The HVAC system of a Redundant Component
60 facility includes multiple air conditioning units with the combined cooling capacity
61 with one redundant unit (N+1). Air-conditioning systems should be designed for
62 continuous operation 7 days/24 hours/365 days/year, and incorporate a minimum of
63 N+1 redundancy in the Computer Room Air Conditioning (CRAC) units. The
64 computer room air conditioners (CRAC) system should be provided with N+1
65 redundancy, with a minimum of one redundant unit for every three or four required
66 units. All air-conditioning equipment should be powered by the standby generator
67 system. Associated with less than 22 hours of downtime/year.

68 Tier 3: Concurrent Maintenance – The HVAC system of a Concurrently
69 Maintainable facility includes multiple air conditioning units with the combined
70 cooling capacity to maintain critical space temperature and relative humidity at design
71 conditions, with sufficient redundant units to allow failure of or service to one electrical
72 switchboard. This level of redundancy can be obtained by either furnishing two sources
73 of power to each air conditioning unit, or dividing the air conditioning equipment
74 among multiple sources of power. The piping system or systems are dual path, whereby
75 a failure of or maintenance to a section of pipe will not cause interruption of the air
76 conditioning system. Redundant computer room air conditioning (CRAC) units should

77 be served from separate panels to provide electrical redundancy. All computer room air
78 conditioners (CRAC) units should be backed up by generator power. Refrigeration
79 equipment with N+1, N+2, 2N, or 2(N+1) redundancy should be dedicated to the data
80 center. Associated with less than 1.6 hours of downtime/year.

81 Tier 4: Fault Tolerant – The HVAC system of a Fault Tolerant facility includes
82 multiple air conditioning units with the combined cooling capacity to maintain critical
83 space temperature and relative humidity at design conditions, with sufficient redundant
84 units to allow failure of or service to one electrical switchboard. If a water-side heat
85 rejection system serves these air conditioning units, such as a chilled water or condenser
86 water system, the components of these systems are likewise sized to maintain design
87 conditions, with one electrical switchboard removed from service. This level of
88 redundancy can be obtained by either furnishing two sources of power to each air
89 conditioning unit, or dividing the air conditioning equipment among multiple sources
90 of power. The piping system or systems are dual path, whereby a failure of or
91 maintenance to a section of pipe will not cause interruption of the air conditioning
92 system. Associated with less than 0.4 hours of downtime/year [4].

93

94 **3.2 Energy Consumption**

95 The energy consumption of the data centers has accounted for 1% of total electricity
96 consumption. Today, data centers are facing soaring energy prices, coupled with
97 increased energy consumption due to increases in server processing power and a greater
98 demand for cooling [5]. Power has become a major expense and therefore, energy
99 efficiency is now a top concern. In 2005, 1.2% of the total U.S. energy consumption
100 was attributed to the server-driven power usage [6]. Of this usage, the energy
101 consumption by the electronic components of the IT made up about 50%, and cooling
102 systems about 40%. In simple terms, 1 kWh of energy consumed by the IT equipment
103 requires another 1 kWh of energy to drive the cooling and auxiliary systems.

104

105 **3.3 Efficiency & Total Cost of Ownership**

106 The data center industry uses the measurement PUE, or power usage effectiveness, to
107 measure efficiency [7]. A PUE of 2.0 means that for every watt of IT power, an
108 additional watt is consumed to cool and distribute power to the IT equipment. A PUE
109 closer to 1.0 means nearly all the energy is used for computing [8].

110 A data center is one of the most financially concentrated assets of any business. The
111 capital and operational costs for the physical infrastructure may be comparable to, or
112 larger than all supported IT assets. Sometimes, decision makers just focus on the
113 upfront costs but are not aware about the long-term costs, especially the operating and
114 maintenance costs [9].

115 Predicting TCO for your physical data center infrastructure is essential to return on
116 investment (ROI) analysis and other business decision processes. Over a 20-year
117 lifespan of the 50 million USD facility, you would spend three to five times the capital
118 costs on operational expenses, with as much as half of that cost—the single largest
119 element on energy. As a result, energy-related electrical and mechanical systems may

120 account for approximately 60 percent of the data center's capital cost and 50 percent of
121 the ongoing operational cost [10].

122 So, it is essential, that close cooperation between your information technology (IT)
123 and facilities team, designer of record, builder, and operations team is a start to assuring
124 that the appropriate trade-offs between capital investment and operating costs are met
125 over the life of the facility, while supporting the budget, growth requirements and green
126 data center goals.

127

128 **3.4 Cooling Process**

129 The sole purpose of data center cooling technology is to maintain environmental
130 conditions suitable for information technology equipment (ITE) operation. Achieving
131 this goal requires removing the heat produced by the ITE and transferring that heat to
132 some heat sink. In most data centers, the operators expect the cooling system to operate
133 continuously and reliably [11]. For decades, computer rooms and data centers utilized
134 raised floor systems to deliver cold air to servers. Cold air from a computer room air
135 conditioner (CRAC) or computer room air handler (CRAH) pressurized the space
136 below the raised floor. Perforated tiles provide a means for the cold air to leave the
137 plenum and enter the main space—ideally in front of server intakes. After passing
138 through the server, the heated air is returned to the CRAC/CRAH to be cooled, usually
139 after mixing with the cold air. The primary benefit of a raised floor, from a cooling
140 standpoint, is to deliver cold air where it is needed, with very little effort, by simply
141 swapping a solid tile for a perforated tile.

142

143 **3.5 Factors affecting Mechanical Systems in Data Center Projects**

144 Heat Load – The most significant factor affecting mechanical system data center
145 projects is heat load. This includes the total heat to be rejected and the density of that
146 heat. Traditionally, data centers have measured heat density in watts per square foot.
147 The construction cost of the data center can be significantly affected by are the design
148 power density and the level of reliability [12]. Design professionals should carefully
149 determine heat loads, and consider developing phased plans for the installation of
150 mechanical and matching cooling equipment to meet IT requirements, so that it makes
151 the most cost-effective sense, requiring infrastructure costs only to be expended when
152 required. Technology Changes – Data center managers will replace servers three times
153 before they replace cooling systems, so the design must be flexible enough to
154 accommodate several technology changes during the life of the facility and must ensure
155 that infrastructure technologies will be able to scale to support future needs [13].
156 Owners, designers, IT data center managers, and operators should also take into
157 consideration, that during the initial start-up and first year of operation of the data center
158 could require the mechanical systems to operate with little or no computing equipment
159 load [14]. Airflow – Careful consideration should be given to airflow produced by the
160 cooling system meet the ITE requirement [15]. Of the numerous ventilation schemes,
161 the team should be able to choose which one is the best for cooling the ITE requirement
162 and minimize airflow distribution problems [16]. Site Location – Climatic Conditions,
163 Temperature, and Humidity. The team will have to determine what the temperature and

164 humidity should be in the space as it affects the operation of the ITE. For new data
165 centers, site location and climatic conditions will also need to be evaluated [17].

166 **4 Research Methodology & Analysis**

167 To better understand mechanical systems projects in data centers, a survey
168 questionnaire was distributed via a web-based service called SurveyMonkey™
169 (<http://www.surveymonkey.com>) to 96 executives. The survey population consisted of
170 IT Managers, Mechanical Designers, Construction Contractors, Facility Engineers,
171 Operations and Maintenance Personnel, and Project Managers representing different
172 phases of project cycle for data center projects. The questionnaire comprised of 27
173 questions and was divided into 4 sections: General Information and Respondents area
174 of knowledge and experience, Overall Management Challenges in Data Centers,
175 Challenges Specific to Data Center Mechanical Systems Projects, and Organization
176 Approach/Management Practices. The Questionnaire survey was open for 21 days.
177 Approximately 30% of the 96 respondents completed the online survey.

178 **4.1 General Information and Respondents Area of Knowledge & Experience**

179 In Section 1, questions 1-5, respondents were asked provide information regarding their
180 domain knowledge and area of experience, preferred acquisition, cause and impacts of
181 budget constraints. Majority of the respondents were Mechanical Designers (43%),
182 followed by Construction Personnel comprising of Project Managers, Builders, CM at
183 Risk, Project Engineers, Construction Quality Control Representatives (36%),
184 Facilities Engineering and Operations Personnel (18%).


185 Design-Build-Build was considered the most appropriate acquisition strategy by
186 45% of the respondents as requirements can be better defined. 38% of respondents
187 chose Design-Build for delivering projects faster. Similarly, 75% of the respondents
188 surveyed indicated that budgets constraints affected their projects. This was attributed
189 to lack of deep-domain expertise of mechanical systems during the assessment phase
190 which resulted in poorly defined requirements and poorly allocated budgets.

191 **4.2 Overall Management Challenges in Data Centers**

192 In Section 2, respondents were queried on management related issues. Questions 6-8
193 validated the need for better project definition during the assessment and planning
194 phases. Most respondents believed poorly defined requirements (undersized cooling
195 and load requirements, not being able to predict capacity and future needs) were the
196 major challenges facing the data center industry. Almost 96% of the respondents
197 confirmed the need to have all stakeholders engaged during the assessment and
198 planning phase. However, when queried whether their team involved all stakeholders
199 during the assessment phase, only 55% confirmed in the affirmative.

200 4.3 Challenges Specific to Data Center Mechanical Systems

201 In Section 3, respondents were asked a total of 13 questions which helped identify
 202 challenges specific to Data Center Mechanical Systems projects. Poor Capacity
 203 Planning, Efficiency, Reliability, Redundancy of equipment, failure to consider exiting
 204 conditions, project constraints, space constraints and colocation, failure to plan for
 205 future growth/over engineering, failure to address airflow issues, and failure to address
 206 temperature and humidity issues, were some of the major challenges identified and are
 207 shown in Figure 1.



208

209 **Fig. 1.** Major Challenges associated with Mechanical System in Data Centers.

210 In this section, respondents emphasized the need to evaluate current technological
 211 trends, especially where legacy systems (ITE and Mechanical) were involved, as
 212 stakeholders were less likely to consider new technology for renovations/upgrades of
 213 such systems. On an average 70% of respondents confirmed, in such projects careful
 214 consideration must be given to technological advances and changes, energy modelling,
 215 energy and water conservation measures, redundancy of equipment, temperature, and
 216 humidity control. Similarly, use of engineering resources to meet industry standards
 217 and manufacturing guidelines, and Building Automation Controls in such projects was
 218 encouraged. Respondents also identified the need to plan for commissioning on critical
 219 components of mechanical systems during assessment phase and then performing
 220 integrated testing/commissioning during the execution phase as critical element.
 221 Respondents indicated that commissioning should be routinely performed during the
 222 maintenance phase. 48% of respondents stressed the need to focus on Maintenance
 223 Planning, be it load balancing, maintaining the cooling system, or simply ensuring that
 224 data center stays clean and well-managed to ensure uptime. Even though, only 18% of
 225 respondents felt the need to evaluate Total Cost of Ownership (TCO), careful

226 consideration should be given as this would eventually help better predict capital and
227 operational expenditure costs, resulting in validated budgets.

228 **4.4 Organizational Approach and Management Practices**

229 The last set of questions gave an insight into the organization approach and
230 management practices. Understanding the culture of an industry or an organization is
231 the key to establishing practices that will lead a team to successful projects and to
232 getting it right the *First Time*. Overall, 88% of the respondents indicated that their
233 organization and management was committed to establishing processes and practices
234 that would result in project success. An area of concern that was noted, is that only
235 58% of the respondents believed that management was committed to self-improvement
236 and allocated enough funds for training.

237 **5 Conclusions**

238 Based on the analysis, some best management practices have been identified.
239 *Organization and Management:* Organizations and Management should support
240 strategic planning to achieve flexibility and scalability and reliability in a data center.
241 Management should support innovation, promote stakeholder engagement, self-
242 improvement initiatives by providing sufficient training opportunities. *Team*
243 *Identification:* As soon as a requirement becomes known, it is imperative that all
244 stakeholder groups are on board. All stakeholders should collaborate, communicate,
245 and be actively engaged in visualizing every aspect of the data center requirements.
246 *Assessment/Project Definition:* Assessments provide all stakeholders with a
247 baseline at which to start. The goals of these assessments are to capture weaknesses in
248 the facility, define requirements and to assist in controlling operational expense
249 (OPEX) or arrive at building and investment costs (CAPEX) and be aware of the total
250 costs of ownership to make a selection that best fits the need of the data center. *Design:*
251 From stakeholder management perspective, ensure that everyone is participating in the
252 selection of the architecture and engineering firm that will provide the design. The first
253 step in designing the cooling and air management systems in a data center is to look at
254 the recommended operating environments for equipment set forth by the American
255 Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE).
256 Another important rule is to always design for flexibility and scalability and design an
257 integrated system that optimizes space allocation, power, and mechanical systems.
258 Build additional capacity into the main electrical components, such as patch panels and
259 conduits, and use higher-gauge electrical wire to accommodate future growth in
260 electrical demand. Data centers often over cool and over control humidity, which results
261 in no operational benefits and increases energy use. Care should be taken to address
262 this issue. Another objective would be to ensure optimal configuration of the data
263 center equipment for improved airflow management, and reduce operational costs. Site
264 selection and climatic trends should be analyzed to invest in systems which would
265 reduce cooling costs. These efforts should be implemented during the definition and

266 design phase. The system should be designed to only support the level of redundancy
 267 required to meet requirements. At a minimum, a monitoring system should be installed
 268 to determine operational efficiency and to diagnose operational problems.

269 *Commissioning/Training/Operations/Maintenance*: Integrated Commissioning
 270 and Training prior to closeout and routinely during the operation and maintenance
 271 phase should be adopted. There is always a need to have a deep-domain expertise in all
 272 the systems that comprise the modern data center, but there is also a need for cross
 273 training on the technology of operations across all stakeholder groups. An IT data center
 274 manager, a Facility engineer, a designer, a builder, or a data center owner should have
 275 some working knowledge of every aspect of the project life cycle to include assessment,
 276 definition, design, construction, commissioning, turnover, operations, maintenance.
 277 This is important, due to the need to work together as a cohesive group across all phases
 278 of the project life cycle. This approach will help deliver an efficient reliable and a
 279 scalable mechanical system that will meet the current and future needs of a data center.

280 References

- 281 1. Alkharabsheh, S., Fernandes, J., Gebrehiwot, B., Agonafer, D., Ghose, K., Ortega, A., ...
 282 Sammakia, B. (2015). A Brief Overview of Recent Developments in Thermal
 283 Management in Data Centers. *Journal of Electronic Packaging*, 137(4), 040801-040801-
 284 19. <https://doi.org/10.1115/1.4031326>
- 285 2. Data Center Challenges | An Executive Data Center Industry Report | Mortenson. (n.d.).
 286 Retrieved May 11, 2017, from [http://www.mortenson.com/company/news-and-](http://www.mortenson.com/company/news-and-insights/data-center-execs)
 287 [insights/data-center-execs](http://www.mortenson.com/company/news-and-insights/data-center-execs)
- 288 3. Data center tier classifications | Consulting-Specifying Engineer. (n.d.). Retrieved June 11,
 289 2017, from [http://www.csemag.com/single-article/data-center-tier-](http://www.csemag.com/single-article/data-center-tier-classifications/cace5d069936d32d1870a72958650ac0.html)
 290 [classifications/cace5d069936d32d1870a72958650ac0.html](http://www.csemag.com/single-article/data-center-tier-classifications/cace5d069936d32d1870a72958650ac0.html)
- 291 4. Use Best Practices to Design Data Center Facilities - DesignBestPractices_127434.pdf.
 292 (n.d.). Retrieved July 24, 2017, from
 293 [file:///C:/Users/manpr/AppData/Roaming/Mozilla/Firefox/Profiles/6k35w8co.default/zoter](file:///C:/Users/manpr/AppData/Roaming/Mozilla/Firefox/Profiles/6k35w8co.default/zoter_o/storage/8FKDN5UU/DesignBestPractices_127434.pdf)
 294 [o/storage/8FKDN5UU/DesignBestPractices_127434.pdf](file:///C:/Users/manpr/AppData/Roaming/Mozilla/Firefox/Profiles/6k35w8co.default/zoter_o/storage/8FKDN5UU/DesignBestPractices_127434.pdf)
- 295 5. DiRamio, D. (2008). Data centers confront energy costs. *Communications News*, 45(11),
 296 36–36.
- 297 6. Li, Z., & Kandlikar, S. G. (2015). Current Status and Future Trends in Data-Center
 298 Cooling Technologies. *Heat Transfer Engineering*, 36(6), 523–538.
 299 <https://doi.org/10.1080/01457632.2014.939032>
- 300 7. Designing a Very Efficient Data Center (n.d.). Retrieved from [https://code.fb.com/core-](https://code.fb.com/core-data/designing-a-very-efficient-data-center/)
 301 [data/designing-a-very-efficient-data-center/](https://code.fb.com/core-data/designing-a-very-efficient-data-center/)
- 302 8. Efficiency: How we do it – Data Centers – Google. (n.d.). Retrieved June 19, 2017, from
 303 <http://www.google.com/about/datacenters/efficiency/internal/#water-and-cooling>
- 304 9. A Holistic Evaluation of Data Center Water Cooling Total Cost of Ownership | Journal of
 305 Electronic Packaging | ASME DC. (n.d.). Retrieved June 21, 2017, from
 306 [http://electronicpackaging.asmedigitalcollection.asme.org.spot.lib.auburn.edu/article.aspx?](http://electronicpackaging.asmedigitalcollection.asme.org.spot.lib.auburn.edu/article.aspx?articleid=2503795&resultClick=3)
 307 [articleid=2503795&resultClick=3](http://electronicpackaging.asmedigitalcollection.asme.org.spot.lib.auburn.edu/article.aspx?articleid=2503795&resultClick=3)
- 308 10. Why understanding data center TCO is critical to your business - QLW12347USEN.PDF.
 309 (n.d.). Retrieved June 21, 2017, from
 310 <http://public.dhe.ibm.com/common/ssi/ecm/ql/en/qlw12347usen/QLW12347USEN.PDFA>

- 311 uthor, F., Author, S.: Title of a proceedings paper. In: Editor, F., Editor, S. (eds.)
312 CONFERENCE 2016, LNCS, vol. 9999, pp. 1–13. Springer, Heidelberg (2016).
- 313 11. Heslin, K. (2015, July 30). A Look at Data Center Cooling Technologies. Retrieved June
314 19, 2017, from [https://journal.uptimeinstitute.com/a-look-at-data-center-cooling-](https://journal.uptimeinstitute.com/a-look-at-data-center-cooling-technologies/)
315 [technologies/](https://journal.uptimeinstitute.com/a-look-at-data-center-cooling-technologies/)
- 316 12. Kurkjian, C., & Glass, J. (2005). Air-conditioning design for data centers-accommodating
317 current loads and planning for the future. *ASHRAE Transactions*, 111, 715.
- 318 13. *IBM_Global_Data_Centre_Study.pdf*. (n.d.). Retrieved July 24, 2017, from [http://www-](http://www-935.ibm.com/services/multimedia/IBM_Global_Data_Centre_Study.pdf)
319 [935.ibm.com/services/multimedia/IBM_Global_Data_Centre_Study.pdf](http://www-935.ibm.com/services/multimedia/IBM_Global_Data_Centre_Study.pdf)
- 320 14. (“10 common data center surprises | Plant Engineering,” n.d.).
- 321 15. *Data Center Best Practices Guide Energy efficiency solutions for high-performance data*
322 *centers - DataCenters_BestPractices.pdf*. (n.d.). Retrieved July 24, 2017, from
323 [file:///C:/Users/manpr/AppData/Roaming/Mozilla/Firefox/Profiles/6k35w8co.default/zoter](file:///C:/Users/manpr/AppData/Roaming/Mozilla/Firefox/Profiles/6k35w8co.default/zotero/storage/XS5SEZM2/DataCenters_BestPractices.pdf)
324 [o/storage/XS5SEZM2/DataCenters_BestPractices.pdf](file:///C:/Users/manpr/AppData/Roaming/Mozilla/Firefox/Profiles/6k35w8co.default/zotero/storage/XS5SEZM2/DataCenters_BestPractices.pdf)
- 325 16. Schmidt, R. R., & Iyengar, M. (2007). Best Practices for Data Center Thermal and Energy
326 Management-- Review of Literature. *ASHRAE Transactions*, 113(1), 206–218.
- 327 17. *Data center design: HVAC systems | Consulting-Specifying Engineer*. (n.d.). Retrieved
328 June 11, 2017, from [http://www.csemag.com/single-article/data-center-design-hvac-](http://www.csemag.com/single-article/data-center-design-hvac-systems/efe0a3f3bef67aabb08362b612933ce.html)
329 [systems/efe0a3f3bef67aabb08362b612933ce.html](http://www.csemag.com/single-article/data-center-design-hvac-systems/efe0a3f3bef67aabb08362b612933ce.html)